TUMKUR DIVISION

757

Dated 19th March 1919.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 12th April 1919, for constructing Taluk Lock-up at Maddagiri. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 to 5 on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. (150) one hundred and fifty only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Taluk Lock-up at Maddagiri, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities for constructing a Taluk Lock-up at Maddagiri, Tumkur Division:—

Serial No.	Items of work	Per	Quantity
1	Earthwork excavation and filling basement	C. yd.	73
2	Concrete in chunam	C. ft.	653
3	Stone in chunam	,,	1,955
4	Burnt brick in clay	,,	2,305
5	Do in mortar	,,	874
6	Do arch work	,,	46
7	Do stone slabs	S. ft.	337
8	Honnewood work wrought and put up	C. ft.	58·20
9	Teakwood lock-up door	S. ft.	171
10	Do panelled door with lock, etc., complete	,,	24
11	Do windows battened and glazed shutters with iron bars	,,	54
12	Do ventilators with iron bars expanded metal including iron complete	,,	50
13	Roofing with pukka terrace	Sq.	6·37
14	Roofing with 1st class Mangalore roofing tiles with teak reepers complete including carriage charges from Tumkur.	,,	5·26
15	Ridge tiles set in mortar	R. ft.	39
16	Cornice (9"×9") thick	,,	235
17	Brick in chunam parapet including plastering	,,	106
18	Chunam plastering	Sq.	47·60
19	White and colourwashing	,,	47·60
20	Pointing with chunam	,,	262
21	Teakwood gate ornamental with iron works	S. ft.	24
22	Flooring with Cuddappa slabs over 3" concrete and cement pointing including carriage charges from Tumkur.	Sq.	6·78
23	Chunam borders	R. ft.	24
24	Finials	Each	2
25	Rain water pipes	,,	10
26	Iron bars ;" *dia* 4' for apertures	,,	2
27	Silicate painting	Sq.	5·48
28	Wood oiling and tarring wood work	L. S.	Rs. 15
29	Clearing site and levelling ground	,,	,, 30
30	Constructing a latrine	,,	,, 58

C. KRISHNA IYENGAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

EXCISE DEPARTMENT.

Notice dated 17th March 1919.

It is hereby notified that 116 "Climax Jars" in stock in the Central Distillery Stores, Bangalore, will be put up to public auction and sold, by the Assistant to the Excise Commissioner in Mysore, at the Distillery premises, at 9 A.M. on Saturday the 12th April 1919. The capacity of the jars is two gallons and they are provided with a turn cork at the bottom. Successful bidders should pay the full amount offered by them on the spot, and on confirmation of sales by the Excise Commissioner, shall remove the jars within three days from the date of receipt of confirmation notice.

T. ROYALOO CHETTY,
For *Excise Commissioner.*